



प्रत्यक्षीतिमपावृणु

No.East/Kolk/Kalna/9 Gr.4795241- 2201 .  
Government of India  
Office of the Superintending Archaeologist  
Archaeological Survey of India  
Kolkata Circle, Kolkata

Kolkata, Dated: 1 JAN 2021

**:: NOTICE INVITING QUOTATION::**

The undersigned on behalf of the President of India do hereby invites the Item rate Quotations in sealed envelope from the eligible Companies/Firms/Agencies who have past experience of similar nature of work in ancient archeological monuments/sites for execution of work for "MW (Conservation) Special Repair to Jalesvara Temple (under Group of Temples 12 Nos.), Kalna, District Purba Barddhaman" within the estimated amount Rs. 1,42,534/- only.

**Details of Items of work**

Item No.	Name of the materials/work	Qnty. Reqd.	Rate to be quoted
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 meters lead.( Lime Sand)	16.96 SqM	SqM
2	Provision for 20 mm lime sand plaster of stair of Jalesvara temple. (1:2) Measurement as same item no 1 (1:2)	16.96 SqM	SqM
3	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 meters lead( Lime Surkhi)	95.48 SqM	SqM
4	Provision for 20mm lime surkhi plaster of (foundation wall & temple wall).Measurement as same item no 3. ( 1:2)	95.48 SqM	SqM
5	Provision for pointing the existing brick pillar with lime surki mortar (1:2) after racking out the damaged pointing where necessary of the surrounding temple pillar.	6.75 SqM	SqM
6	Demolishing lime concrete manually/ by mechanical means and disposal of material within 50 meters lead as per direction of Engineer in-charge.. (20.94m <sup>2</sup> x.075=1.570m <sup>3</sup> )	1.58 SqM	SqM
7	75mm thick terraced baranda & roof of lime concrete with stone lime, surki & 32 mm down Jhama khoa(2:2:7) (2 lime putty:2 surki: 7 jhama khoa) Measurement as same item No 6.	1.58 SqM	SqM
8	Provision for design brick work of three tower Jalesvara temple	0.73 SqM	SqM
9	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete On steel work	83.4 SqM	SqM



10	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	29.88 SqM	SqM ,
11	White washing with lime to give an even shade	29.88 SqM	SqM
12	Provision for erecting & dismantling of bamboo scaffolding for execution of work. only Item No 8.	Lumpsum	LS
13	Provision for fixing Direction board	1 No.	Each


The quotation should be addressed in favour of **Superintending Archaeologist, Archaeological Survey Of India, Kolkata Circle, Salt Lake city, Kolkata-700064** and should be reached to this office latest by **18:00 Hrs. of date. 08.01.2021** (the Quotation will be opened on 11.01.2021) subject to the following terms and conditions.

**Terms & Conditions:-**

- i. Contractors/Suppliers/Firms/Agencies should be registered with the appropriate registration authority.
- ii. Contractors/Suppliers/Firms/Agencies should be registered with GST and latest GST clearance certificates.
- iii. Contractors/Suppliers/Firms/Agencies should have Labour registration certificate along with EPF and ESI registration.
- iv. Contractors/Suppliers/Firms/Agencies should have valid PAN, GSTIN
- v. Contractors/Suppliers/Firms/Agencies should have past experience in conservation works of Ancient Archaeological Monuments /sites for the last 03 years (Prior to the current financial year).
- vi. The rates as quoted should hold well for up to March, 2021. No change in the rates or modification thereof will be permitted.
- vii. In all cases payment will be made through bank account.
- viii. No T&P etc. will be provided by the Department regarding execution of work.
- ix. Execution shall have to be completed within **30 days** from the date of award of work.
- x. Payment will be made on submission of bill after execution of the job subject to verification of Departmental Gazette Officer/Engineer or in-charge of the concerned site.
- xi. The undersigned does not bind him to accept the lowest rate and reserve the right to reject or accept or prefer any quotation either in full or in part without assigning any reason thereof in the interest of public services.
- xii. The undersigned will not be responsible for loss of any quotation in transit or otherwise.

**Following should be submitted alongwith the Bid**

- i. Copies of the valid Registration Certificate.
- ii. Copy of PAN card.
- iii. Copies of the GST registration certificate along with GST clearance certificate of last month.
- iv. Declaration regarding black listing as per format attached in Letter Head.
- v. Copies of Experience certificate of having successfully completed similar works for the last 3 years (Prior to the current financial year) in Ancient Archaeological Monuments/ sites.
- vi. Copies of Labour Registration certificate along with EPF an ESI registration certificate.

  
 (Dr. Shubha Majumder)  
 Superintending Archaeologist (I/C)

Copy to:

1. Office Notice Board of ASI, Kolkata Circle.
2. Office Notice Board of Kalna Sub-Circle Office
3. Website of ASI, Kolkata Circle.