

1

**F. No.M3/KC-2/08/2016-17**  
**Government of India**  
**Office of the Superintending Archaeologist**  
**Archaeological Survey of India**  
**Kolkata circle, C.G.O. complex (4<sup>th</sup> floor)**  
**Block-DF, Sector-I, Salt Lake City, Kolkata – 700 064.**  
**Web Site : [www.asi.nic.in](http://www.asi.nic.in) / [www.asikolkata.in](http://www.asikolkata.in)**

Dated:

**OPEN TENDER NOTICE**

**NAME OF THE WORK: EXECUTION OF WORKS AT CURRENCY BUILDING, KOLKATA  
UNDER S.R.(PLAN) TO RESTORTION OF SOUTHERN SIDE OF  
CURRENCY BUILDING, KOLKATA.**

The Superintending Archaeologist, Archaeological Survey of India, Kolkata Circle, Kolkata, on behalf of the President of India invites item rate tender in sealed cover from the approved contractors for the execution of works at Currency Building, Kolkata under estimate **S.R.(PLAN) TO RESTORTION OF SOUTHERN SIDE OF CURRENCY BUILDING, KOLKATA** who have past experience of successfully completing similar type EXEUCUTION OF WORKS at **CURRENCY BUILDING, KOLKATA OR ELSEWHERE** as per detailed below up-to 14.00 hours on **03.07.2017** which will be opened on the same day at 14.30 hours in the Office of the Superintending Archaeologist, Archaeological Survey of India, Kolkata Circle, C.G.O. Complex (4<sup>th</sup> floor), Block-DF, Sector-I, Salt Lake City, Kolkata-700064.

Sl.No.	Details of work	Quantity	Rate
1.	Erecting & dismantling of tubular scaffolding for execution of outside & inside courtyard area of Currency Building.	6019.52 Sq.m	Per Sq.m
2.	Covering the building by good quality polythene sheet, hessian cloth etc. on the tubular frame works to prevent ingress of rain water into the building masonry during repair etc.	One item	
3.	Scraping of moss, blisters etc. thoroughly from exterior surface of walls necessitating the use of scraper, wire brush etc.	3009.76 Sq.m	Per Sq.m
4.	Stripping off worn out plaster and raking out joints o walls, ceilings etc. upto any height and in any floor including removing rubbish within a lead of 75m.	2106.83 Sq.m	Per Sq.m
5.	Dismantling terraced roof, taking out carefully tiles with beams, joists, tees or burgahs covering floors below sorting and stacking serviceable materials at site within a lead of 75m.	501.91 Sq.m	Per Sq.m
6.	Removal of rubbish from the working site and disposal of the same beyond the compound in conformity with Municipal/Corporation Rules for such disposal loading into truck and cleaning the site.	123.93 Cum	Per Cum

7.	Brick work with 1 <sup>st</sup> class bricks in lime and surki , mortar(1:2) as per original on the Southern side of Currency Building.	4.45 Cum	Per Cum
8.	25 mm thick sand and lime (3:1) plaster including rounding off or chamfering corners as directed and raking out joints where necessary.	2121.99 Sq.m	Per Sq.m
9.	12.5mm thick sand and lime plaster (3:1) over the previous layer as mentioned in the measurement of item No. 8	2121.99 Sq.m	Per Sq.m
10.	10 cm thick lime terracing on roof with lime concrete 2:2:7(2 lime paste: 2 Surki: 7 Brick Khoa) laid in proper slope, thoroughly beaten and cured including top finishing, providing ghoondies at junction with parapet etc., shaping and finishing at mouths of rain water pipes complete.	501.91 Sq.m	Per Sq.m
11.	Taking out the bulged out marble tiles & resetting the same with lime surki mortar (1:3) of the courtyard.	26.60 Sq.m	Per Sq.m
12.	Stitching cracks in brick wall by carefully cutting and face brick 25pmm long, 75 mm thick and 125 mm deep into the wall, cleaning the gap and filling up the same with sound new brick, carefully set in cement mortar(1:3) including mending good damages and finishing the surface to match with adjacent areas complete.	200 Nos.	-----
13.	Stitching cracks on floor by 35 mm thick artificial stone in floor of the Northern side mezzanine floor with cement concrete(1:2:4) with stone chips with 3mm thick topping made with ordinary cement including smooth finishing by providing M.S. grating (1.00mx0.60m of 0.30m apart) of approved design laid underneath the concrete to prevent further cracks.	-----	-----
13(A)	M.S.grating on cracks (1.00m x 0.60m of 0.30m apart)	21.60 Rmt	Per Rmt
13(B)	35mm thick artificial stone in floor	12.96 Sq.m	Per Sq.m
14.	Supplying, fitting, fixing C.I.down pipes(150mm dia internal) in position with clamp, nail etc. with jointing materials including existing holes, mending good damages outside wall of Currency Building.	201.60 Rmt.	Per Rmt.
15.	Removing choking of rain water down pipes with split bamboo.	135.00 Rmt	Per Rmt.
16.	Changing the damaged grill of the Southern side grill gate including welding the same with hammering, tempering, grinding etc. as per existing design.	One item	-----

17.	Ordinary Cement Concrete (mix 1:2:4) with graded stone chips (20mm nominal size) excluding shuttering and reinforcement, if any, in ground floor drain of northern side passage area of the building.	0.74 Cum	Per Cum
18.	15mm thick plaster with (4:1) sand and cement mortar including rounding off or chamfering corners in drain of Northern side passage area of the building .	103.60 Sq.m	Per Sq.m
19.	1.5mm thick neat cement punning in drain of Northern side passage area of the building over newly plastered area.	103.60 Sq.m	Per Sq.m
20.	7.5 cm deep & 5cm width cutting grooves on the Northern side outer wall in plinth level for layout the dampness of the wall including mending the said grooves properly.	One item	-----
21.	White washing for 2 coats including cleaning & smoothening surface of outer portion of Currency building.	3009.76 Sq.m	Per Sq.m
22.	Applying 2 coats Synthetic Enamel paint over a coat of priming on the Wooden doors & Windows after cleaning & smoothening surface by sand papering etc. of outside doors and windows of Ground floor, 1 <sup>st</sup> floor & 2 <sup>nd</sup> floor of Currency Building.	----	---
22A	Priming one coat.	753.09 Sq.m	Per Sq.m
22B(1)	Painting 2 coats with best quality Synthetic Enamel paint. Timber surface.	630.90 Sq.m	Per Sq.m
22B(2)	Painting 2 coats with best quality Synthetic Enamel paint. Steel/Metal surface.	112.19 Sq.m	Per Sq.m
23.	Arresting the re-growth of Micro-Vegetation, 2% solution of fungicide in water to be applied over the whole surface with a double coat (wet-on-wet) of a mixture of wacker BS-290 in the solvent Mineral Turpentine Oil (MTO) in the ratio 1:12 to be applied over the surface.	501.91 Sq.m	Per Sq.m
24.	Changing of the damaged & broken glass panes of the doors and windows including changing of damaged putty of all the glass panes of doors and windows.	One item	----
<b>ESTIMATED COST OF Rs. 26,27,248/- (RUPEES TWENTY SIX LAKHS TWENTY SEVEN THOUSAND TWO HUNDRED AND FORTY EIGHT ONLY)</b>			

\* Prior experience of similar execution of work for Heritage Building status and specific to the items entered above within two (2) years are pre-requisite of the applicant/ tender, without which the tender papers will not be issued.

6

Tender of the contractors/suppliers who will not deposit earnest money **Rs. 65,700/- (Rupees Sixty five thousand and seven hundred only)** vide **Demand Draft from any Nationalized Bank in favour of the "Superintending Archaeologist, Archaeological Survey of India, Kolkata circle, Kolkata"** and copies of the Registration Certificate and latest Income tax clearance certificate/Vat clearance certificate as per notification of Directorate of commercial taxes, West Bengal vide no. 1290 F.T. dated 31.07.2006 shall be summarily rejected.

The competent authority reserves the right to accept or reject any or all tenders without assigning any reasons thereof. Conditions & Tender Forms can be obtained from the office of the Superintending Archaeologist, Archaeological Survey of India, Kolkata Circle, Kolkata between 10.00 to 16.00 hours on all working days on payment of **Rs.1000/-(Rupees One thousand only)** (non-refundable) **upto 29.06.2017**. Last date of application for tender form is **28.06.2017**.

In case of public holiday declared on the opening date of Tender the same would be opened on the next working day.

**CONTRACTORS/SUPPLIERS MUST DROP THE TENDERS DIRECTLY TO THIS OFFICE IN THE TENDER BOX WITHIN THE STIPULATED DATE.**

Execution of work should be completed within **120 days** from the date of issue of work order.

  
Superintending Archaeologist 05/6/17

F. No.M3/KC-2/08/2016-17 - 280

Dated : - 5 JUN 2017

To

1. OFFICE NOTICE BOARD, A.S.I., Kolkata Circle, Kolkata.
2. Office Notice Board, A.S.I., Kolkata Sub Circle-II, Currency building, Kolkata.
- ✓ 3. The Web Manager, A.S.I., New Delhi.
4. Office Copy